

FY 19/20 CMAQ/STBG Programmed Projects (as of April 30, 2020)

LEAD AGENCY	PROJECT ID	PROJECT TITLE	PROJECT DESCRIPTION	Fed Fund	FY19/20	Project Status (as of January 2020)	Project Status (as of May 2020) if left blank, no change
Clovis	FRE170003	Nees Ave Street Improvements - Minnewawa to Clovis	On Nees Ave from Minnewawa to Clovis Ave; road widening and reconstruction, installation of curbs, gutters, returns, bicycle lanes, sidewalk, adjusting existing utilities, modifying existing traffic signal signalization, installing traffic striping, markings and signage, and street lights.	STBG	\$340	On track to obligate in 19/20	
Clovis	FRE170005	Villa-Minnewawa Street Improvements from Herndon to Alluvial	Villa-Minnewawa Ave from Herndon Ave to Alluvial Ave. Road widening reconstruction, installation of curbs, gutters, returns, bicycle lanes, sidewalk, median island, adjustment of existing utilities, installation of landscaping, irrigation, traffic striping, marking and signage, and street lights.	STBG	\$292	On track to obligate in 19/20	
Clovis	LSTMP62	Temperance Ave Rehabilitation from Shaw to Barstow	Temperance Avenue from Shaw Avenue to Barstow Avenue; Road rehabilitation: grinding, new asphalt concrete, adjusting utilities, constructing ADA and signal pedestrian improvements, installing traffic devices and loops, and re-striping.	STBG	\$720	Obligated - Oct 2019	
Clovis	LSTMP616	Clovis Ave Rehab: Nees to Alluvial	Clovis Ave from Nees Ave to Alluvial Ave; Street rehabilitation, including curb, signal, signage, detector loops, and striping.	STBG	\$89	Obligated - Dec 2019	
Clovis	LSTMP618	Barstow Ave Rehab: Minnewawa to Clovis	Barstow Ave from Minnewawa Ave to Clovis Ave; Road rehabilitation, including curb, signal, signage, detector loops, and striping	STBG	\$65	Obligated - Dec 2019	
Clovis	LSTMP619	Shaw Ave Rehab: Sunnyside to Fowler	Shaw Ave from Sunnyside Ave to Fowler Ave; Street rehabilitation, including curb, signal, signage, detector loops, and striping.	STBG	\$113	Obligated - Dec 2019	
Clovis	LSTMP631	Armstrong & Nees Traffic Signal	At the intersection of Armstrong and Nees; Install traffic signal, loop detectors, communication equipment, cameras, right-turn lanes, replace access ramps, and grading/paving	CMAQ	\$61	Obligated - Oct 2019	
Clovis	LSTMP632	Shepherd & Peach Traffic Signal	At the intersection of Shepherd and Peach; Install traffic signal, loop detectors, communication equipment, replace access ramps, and grading/paving	CMAQ	\$59	Obligated - Dec 2019	
Clovis Total					\$1,739		
Coalinga	LSTMP611	Polk Street Rehabilitation: Elm to 5th	Polk Street from Elm Ave to 5th Street; Rehabilitation to replace asphalt pavement, install new sidewalk, curb, and gutter	STBG	\$505	On track to obligate Spring 19/20	delayed to 20/21 due to budget constraints.
Coalinga	LSTMP633	West Coalinga Multi Use Trail	Monterey Ave between Lucille Ave and Cambridge Ave; Phase 1 of pedestrian and bicycle facilities	CMAQ	\$461	On track to obligate Spring 19/20	
Coalinga	LSTMP673	Coalinga SRTS Sidewalk Gap Closure & Ped Improvements	W/S of California St: Washington St to Harvard Ave; E/S of California St: Baker St to Cambridge ave	ATP/ CMAQ	\$550	On track to obligate in 19/20	
Coalinga	LSTMP664	Sunset St Rehabilitation: Polk to Van Ness	Sunset St from Polk St to Van Ness Ave; Rehabilitate, resurface, and replace existing AC pavement, grading base material, construct ADA ramps, sidewalks, curb and gutter, driveways, valley gutters, storm drain, electrical pull-boxes, traffic striping, and traffic signage.	STBG	\$500		EPSP from 20/21. On track to obligate in 19/20. Pending FCOG amendment 18-10
Coalinga Total					\$1,511		
FAX	LSTMP634	Southwest Fresno Service Expansion - Route 38	Southwest Fresno transit service expansion demonstration project on route 38; to include three years of operating support	CMAQ	\$855	On track to obligate Spring 19/20	
FAX Total					\$855		
Firebaugh	FRE190004	8th St Pedestrian Facilities Rehab and Construction: P to SR33	8th Street from P St to SR33; Rehab and Construction of pedestrian facilities, including sidewalks, curb, gutter, and ramps	STBG	\$268	On track to obligate in 19/20	
Firebaugh Total					\$268		
Fowler	LSTMP613	Adams Ave Rehabilitation: 5th to Merced	Adams Ave from 5th St to Merced St; Rehabilitation of pavement and pedestrian facilities	STBG	\$384	On track to obligate in 19/20. EPSP from 20/21	
Fowler	LSTMP636	S. Fowler Ave Sidewalks	Westside of S. Fowler Ave between South Ave and Fresno St; Construct sidewalks	CMAQ	\$117	On track to obligate in 19/20. EPSP from 20/21	
Fowler Total					\$501		

Fresno	FRE170024	Olive Ave Streetscape	Olive Ave from Yosemite to Roosevelt; streetscape, sidewalk and median improvements including high visibility crosswalks, curb extensions, widened sidewalks, minimized/reduced driveway curb cuts, new landscaping, and median widening and repair.	STBG	\$1,273	On track to obligate Spring 19/20	
Fresno	LSTMP538	Divisadero/Mariposa Traffic Signal	Divisadero and Mariposa intersection; traffic signal installation and relocation of crosswalk.	CMAQ	\$553	Obligated - Nov 2019	
Fresno	LSTMP544	ITS Installation and synchronization of Ventura/Kings Canyon from Van Ness to Chestnut	Ventura/Kings Canyon from Van Ness Ave to Chestnut Ave; Install adaptive ITS system, cabinets, fiber & network, cameras, detection, and synchronize corridor.	CMAQ	\$1,796	On track to obligate Spring 19/20	obligated - March 2020
Fresno	LSTMP545	ITS Installation and synchronization of Blackstone/Friant from McKinley to Shepherd	Blackstone/Friant Ave from McKinley Ave to Shepherd Ave; Install adaptive ITS system, upgrade detection, and synchronize corridor.	CMAQ	\$2,568	Obligated - Nov 2019	
Fresno	LSTMP546	ITS Installation and synchronization of Blackstone/Abby from Divisadero to McKinley	Blackstone/Abby Ave from Divisadero Ave to McKinley Ave; Install adaptive ITS system, vaults, cabinets, cameras, detection, and synchronize corridor.	CMAQ	\$1,505	EPSP CON from 20/21 to 19/20 will OB CON in Feb 2020	obligated - March 2020
Fresno	LSTMP553	First Street AC Overlay from Alluvial to Herndon	First Street from Alluvial to Herndon Ave; AC Overlay and installation of curb ramps, signal loop detectors, signage and striping.	STBG	\$884	Obligated - Nov 2019	
Fresno	LSTMP557	Jensen Ave AC Overlay from SR41 to MLK	Jensen Ave from State Route 41 to Martin Luther King Jr.; AC Overlay and installation of curb ramps, signal loop detectors, signage and striping.	STBG	\$96	On track to obligate in 19/20 - Pending FCOG Amendment	obligated - March 2020
Fresno	LSTMP558	Ashlan Ave AC Overlay from First to Millbrook	Ashlan Avenue from First Street to Millbrook Avenue; AC Overlay and installation of curb ramps, signal loop detectors, signage and striping.	STBG	\$502	Obligated - Nov 2019	
Fresno	LSTMP559	Inyo St AC Overlay from Van Ness to P St	Inyo Street AC Overlay from Van Ness Ave to P Street; AC Overlay and installation of curb ramps, signal loop detectors, signage and striping.	STBG	\$595	Obligated - Nov 2019	
Fresno	LSTMP617	Bullard Ave AC Overlay: First to Cedar	Bullard Ave from First St to Cedar Ave; AC Overlay, plus curb ramp improvements, signal loop detectors, signage, striping, and Class II bike lane	STBG	\$1,504	On track to obligate in 19/20 - Pending FCOG Amendment	On track to obligate in 19/20 - FCOG Amendment complete.
Fresno Total					\$11,276		
Fresno County	FRE150024	Adams from Cherry to Clovis; Shoulder Improvements	Adams Avenue from Cherry Avenue to Clovis Avenue; Shoulder Improvements. Construct 4-foot wide paved shoulders on each side of existing 24-foot travel-way.	CMAQ	\$751	On track to obligate in 19/20 but could potentially be delayed	Delayed to 22/23 - project in eminent domain
Fresno County	LSTMP535	Jensen Ave Shoulder Improvements from Dickensen to Madera Ave	Jensen Ave from Dickensen to Madera Ave. Shoulder improvements; construct 4-foot wide paved shoulders on each side of existing 24-foot travel way.	CMAQ	\$1,615	Pending scope change that will require additional funds and FCOG Amendment. Direction to be provided from County.	Delayed to 21/22- pending ROW
Fresno County	LSTMP623	Fowler and Olive Traffic Signal	Intersection of Fowler Ave and Olive Ave; traffic signal installation and roadway improvements	CMAQ	\$60	On track to obligate in 19/20	Delayed to 20/21 - pending NEPA approval
Fresno County	LSTMP643	Goodfellow Ave Shoulder Improvements from Channel to Reed	Goodfellow Ave from 0.71 E/O Channel Rd to Reed Ave. Shoulder improvements; construct 8-foot wide paved shoulders on each side of existing travel way.	CMAQ	\$44	On track to obligate in 19/20	Delayed to 20/21 - pending NEPA approval
Fresno County	LSTMP644	Mountain View Ave Shoulder Improvements from Fowler to McCall	Mountain View Ave from Fowler Ave to McCall Ave. Shoulder improvements; construct 8-foot wide paved shoulders on each side of existing travel way.	CMAQ	\$44	On track to obligate in 19/20	Delayed to 20/21 - pending NEPA approval
Fresno County	LSTMP620	McCall Ave Overlay: SR 180 to Shaw	McCall Ave from 0.3 miles n/o SR 180 to Shaw Ave; AC Overlay.	STBG	\$2,055		EPSP project from FY 20/21
Fresno County Total					\$2,055		
Huron	FRE150008	Lassen Avenue Union Pacific Railroad Crossing Sidewalks	Lassen Avenue (SR 269) to UPRR crossing between 9th Street and 10th Street; Construct pedestrian sidewalks	STBG	\$145	On track to obligate in 19/20	Delayed to 20/21 - pending UPRR
Huron Total					\$0		
Kerman	LSTMP614	Kearney Blvd Rehab & Reconstruction: Madera to Vineland	Kearney Blvd from Madera Ave (SR145) to Vineland Ave: Pavement rehab and partial reconstruction, including curb, gutter, sidewalk, ADA ramps, signage, striping, and pedestrian crossing at 8th and Kearney.	STBG	\$501		
Kerman Total					\$632		
Kingsburg	LSTMP543	Madsen Ave Bike Trail from Stroud to Kamm	East Side of Madsen Ave from Stroud Ave to Kamm Ave; Construct bike trail	CMAQ	\$233	On track to obligate in 19/20 but could potentially be delayed	

Kingsburg	LSTMP637	18th Ave Sidewalks from Sierra to Stroud	West-side of 18th Ave from Sierra St to Stroud Ave; Construct sidewalks	CMAQ	\$169	On track to obligate in 19/20. EPSP from 20/21	
Kingsburg	LSTMP656	Mehlert Ave Rehabilitation: 12th to 14th	Mehlert Ave from 12th Ave to 500' e/o 14th Ave, Rehabilitate pavement and pedestrian facilities	STBG	\$140	On track to obligate in 19/20. EPSP from 20/21	
Kingsburg Total					\$542		
Mendota	FRE190003	Citywide Railroad Crossing Improvements	SR33 RRRG between Bass Ave and SR 180 intersection, 9th St RRRG between Marie St and Naples St, and W. Belmont Ave RRRG between Marie St and SR180/N San Benito Ave; Improve Railroad corridor by installing new concrete panels, median channelizers, and roadway construction	STBG	\$450	On track to obligate in 19/20	Delayed to 20/21 - pending UPRR
Mendota	FRE190014	Bass & Barboza Roundabout	At the intersection of Bass & Barboza construct roundabout.	STBG CMAQ	\$347 \$530	On track to obligate in 19/20	
Mendota Total					\$877		
Orange Cove	FRE190005	E. Railroad Ave Culvert Replacement	East Railroad Ave from Thirds St to 200' West; Replace existing culverts, construct paving and install storm drain pipeline	STBG	\$11	On track to obligate in 19/20	
Orange Cove	LSTMP548	D Street Sidewalk from 9th to Center	D Street from 9th Street to Center Street near McCord Elementary; construct sidewalk and ramps on south side of street.	CMAQ	\$66	On track to obligate in 19/20	
Orange Cove Total					\$77		
Parlier	LSTMP540	Manning Ave Sidewalk and Bike Lane from Academy to Mendocino	Manning Ave from Academy to Mendocino. Construction of sidewalk, curb and gutter, and a Class II bike lane along the northside of Manning Ave where the existing sidewalk ends 200 ft east of Academy Ave to 200 ft west of Mendocino Ave.	CMAQ	\$348	On track to obligate in 19/20 - Pending FCOG Amendment	
Parlier Total					\$348		
Reedley	FRE130016	Manning Avenue Reconstruction/Overlay from I St to Buttonwillow	Manning Avenue from I Street to Buttonwillow Avenue; overlay and slurry seal pavement, traffic signal retrofit and synchronization, medians, lighting, bike lanes, sidewalks and ramps, landscaping, signage, and striping. 3-stage project: Stage 1, I Street to Frankwood Ave, Stage 2: Frankwood to Columbia, Stage 3: Columbia to Buttonwillow	STBG	\$1,141	On track to obligate in 19/20	
Reedley	FRE190012	Reedley CNG Street Sweeper Replacement	Purchase 1 CNG Street Sweeper	CMAQ	\$348	Pending Buy America waiver - will be delayed	
Reedley	LSTMP541	East Ave Sidewalk from Lincoln Ave to August Ave	East Ave from Lincoln Ave to August Ave. Construct 1,900 feet of sidewalk, install/upgrade curb ramps to meet ADA standards.	CMAQ	\$378	On track to obligate in 19/20	
Reedley	LSTMP621	Manning Ave Sidewalks: Frankwood to Reed	Manning Ave from Frankwood Ave to Reed Ave; Install sidewalk on north side of street.	CMAQ	\$207	On track to obligate in 19/20	
Reedley	LSTMP687	Reed Ave Sidewalks from I to 8th	Westside of Reed Ave; I St to 8th St: Install sidewalks.	CMAQ	\$50	On track to obligate in 19/20	
Reedley Total					\$1,776		
Sanger	FRE170004	Bethel Ave Rehabilitation from Annadale Ave to Jensen Ave	Bethel Ave from Annandale Ave to Jensen Ave. Grind/Overlay, Widening and bicycle lanes. Replacement of existing damaged curb and gutter, sidewalk, and other concrete improvements, and construction of curb ramps where they are non-compliant.	STBG	\$781	On track to obligate in 19/20. EPSP from 21/22	obligated - March 2020
Sanger	LSTMP547	Sanger Sidewalk Gap Closure Project	In the City of Sanger, construction of concrete sidewalk pedestrian facilities at various locations.	CMAQ	\$185	On track to obligate in 19/20	
Sanger	LSTMP615	Greenwood Ave Rehab: Jensen to Canal (Sanger)	In the City of Sanger on Greenwood Ave from Jensen Ave to Canal Drive; Pavement rehabilitation and reconstruction, including curb, gutter, sidewalk, curb ramps, signage, and striping.	STBG	\$648	On track to obligate in 19/20	
Sanger	LSTMP622	Faller Ave Rehab: Church to Florence	Faller Ave from Church Ave to Florence Ave; Pavement rehabilitation, including curb, gutter, sidewalk, and roadway signage/striping	STBG	\$410	On track to obligate in 19/20	
Sanger	LSTMP649	Faller Ave & Lincoln Park Sidewalks	Construct Sidewalks at the following locations: N/S of Cherry Ave from Park Ave to P St W/S of P St from Cherry Ave to 230 ft North of Cherry E/S of Park Ave from Cherry Ave to 180 ft North of Cherry E/S of Faller Ave from Edgar Ave to 750 ft South of Edgar S/S of Edgar Ave from Faller Ave to 240 ft East of Faller E/S of Faller Ave from I St to 470 ft South of I St Faller Ave from I St to 240 ft North of I St W/S of Faller Ave from Annadale to 140 ft South of Annadale	CMAQ	\$237	On track to obligate in 19/20	

Sanger Total					\$2,261		
Selma	LSTMP584	Selma Arterial Street Rehabilitation	McCall from Floral to Dinuba; Orange from Floral to Nelson; Nelson from Highland to Thompson; Rose from McCall to Country Rose; Second from E. Front to High - Patch longitudinal cracking with Hot Mix Asphalt (HMA) in 4-ft. strips along Arterials and Major Collectors. Crack seal all joints and cracks, place type II slurry seal over entire road width and restripe.	STBG	\$655	On track to obligate in 19/20	
Selma	LSTMP585	East Floral Ave Rehabilitation	East Floral Ave from Union Pacific Railroad (UPRR) to McCall Ave; Rehabilitation by removing/reclaiming the existing roadway section and replacing it with a Hot Mix Asphalt (HMA) overlay	STBG	\$350	Obligated	
Selma	LSTMP642	Selma Alley Paving 2018 - Various Locations	Alley between Chestnut/Floral from Logan to w/o McCall, Alley between Lee/McCall from Floral to Chestnut, and Alley between Shaft/Cleveland from Rose to Arrants; Pave unpaved alley ways.	CMAQ	\$349	On track to obligate in 19/20	
Selma Total					\$1,354		
Grand Total					\$26,072		
FFY 19/20 OA Target					\$27,758		
Percent Estimated to OA Target					93.9%		